6	Carriage of Mixed Materials complete as per specifications.	Cum	95.25	51.85	Rupees Fifty One and Eighty Five Paise Only
7	Removing B.S.Slab of drain and stacking etc., complete as per specifications.	Sqm	70.2	49.86	Rupees Forty Nine and Eighty Six Paise Only
8	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	8.78	4190.32	Rupees Four Thousand One Hundred Ninety and Thirty Two Paise Only
9	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	8.78	4667.05	Rupees Four Thousand Six Hundred Sixty Seven and Five Paise Only
10	Refixing stone slabs of drains and pointing in CM 1:3 etc., complete as per specifications.	Sqm	70.2	69.69	Rupees Sixty Nine and Sixty Nine Paise Only
11	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete as per specifications.	Sqm	37.8	341.72	Rupees Three Hundred Forty One and Seventy Two Paise Only
12	Providing & fixing pre cast solid concrete Kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete as per specifications.	No	536	314.86	Rupees Three Hundred Fourteen and Eighty Six Paise Only
13	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications.	Cum	381	77.85	Rupees Seventy Seven and Eighty Five Paise Only

B.T. Ramireddy
Signature of the Contractor

Executive Engineer,
Dasarahalli Division,